

HASSAN DIVISION.

Notice dated 5th January 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division up to 2 P.M., on the 30th January 1928, for constructing General Hospital at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed Tender for constructing General Hospital at Hassan, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Approximate quantity for constructing General Hospital at Hassan.
(Administrative Block.)

No.	Items of work	Per	Ground floor quantity	First floor quantity
1	Earthwork excavating foundation and filling the basement.	C.yds.	291	...
2	Concrete in mortar	C.ft.	2122	...
3	Burnt stone in mortar foundation and basement ...	"	7247	...
4	Burnt brick in mortar superstructure ..	"	8111	5956
5	Brick in mortar arch work	"	924	114
6	Burnt stone slabs 6" thick dressed	S.ft.	612	170
7	Plastering with chunam.	Sqr.	145'93	117'25
8	White and colour washing	"	145'93	117'25
9	Cement pointing to basement	"	10'30	...
10	Teakwood doors with $\frac{3}{4}$ " panel shutters $1\frac{1}{2}$ " thick segmental glazed shutters with iron fittings, etc., complete.	S.ft.	714	519
11	Teakwood windows panelled shutters outside and glazed shutters inside with iron bars and iron fittings, etc.	"	513	464
12	Teakwood glazed fan lights, complete	"	105	...
13	Silicate painting two coats, light blue or green ...	Sqr.	30'30	22'84
14	Rolled steel girders and joists including railway freight and hoisting charges.	Cwts.	224	171'71
15	Boxing up girders with cement concrete and plastering	C.ft.	78	46
16	Jack arch terrace without flat tiles, complete ..	Sqr.	27'44	...
17	Jack arch terrace with two course of flat tiles, complete	"	10'00	21'83
18	Flooring with Cuddapah slabs on 9" square Mangalore tiles over 3" concrete bed and cement pointing.	"	31'43	...
19	Flooring with 9" square Mangalore tiles over terrace bed and cement pointing.	"	...	26'94
20	Plain cornice with string course	R.ft.	416	...

No.	Items of work	Per	Ground floor quantity	First floor quantity
21	Mortar architrave 9" wide and 3" thick ...	R.ft.	120	...
22	Preparing mortar base and caps of piers of arch ...	"	144	...
22a	Plain architrave 9" to 6" wide and 2" thick ...	"	376	...
23	Masonry plain parapet wall with plastering 2½' high ¾' thick.	"	178	266
24	Armoured concrete partition wall with doorway and plastering, complete.	S.ft.	294	695
25	Brick circular columns including plastering, base, caps, etc., complete 1' diameter.	R.ft.	24	220
26	Cudapah slabs fixing in mortar ...	S.ft.	911	587
27	Providing sanitary fittings ...	Lump sum	Lump sum	Lump sum
28	Do water supply ...	Lump sum	Lump sum	Lump sum
29	Laying foundation stone ...	Lump sum	Lump sum	Lump sum
30	Constructing a stair case including steps rails platform with varnish, etc.	Lump sum	Lump sum	Lump sum
31	Drainage arrangement ...	Lump sum	Lump sum	Lump sum
32	Doric entablature including cornice, frieze architrave, etc.	R.ft.	...	268
33	Preparing mortar architrave and top cornice with pediment for windows.	"	...	288
34	Preparing mortar rosetts ...	Each	...	10
35	Teakwood railings with painting on base ...	R.ft.	...	74

Approximate quantity for constructing Out-patients Block and Operation Theatre for Out-patients Block in the New District Hospital at Hassan.

No.	Items of work	Per	Out patients Block quantity	Operation Theatre quantity
1	Earthwork excavation and filling in ...	C.yds.	138	43
2	Concrete in lime mortar (with stone jelly) ...	C.ft.	1613	493
3	Burnt stone in chunam ...	"	2732	2428
4	Burnt brick in chunam ...	"	5465	...
5	Burnt stone slabs of 4½" thick dressed and set in mortar.	S.ft.	290	30
6	Burnt brick in chunam archwork ...	C.ft.	259	...
7	Circular pillars of lime concrete 1: 2½ mixed in 1/12 part of neat cement (in blocks 8' high and of dr. 13½") with double ground lime mortar ¾" thick with 1/12 neat cement and forming base and cap as per design.	R.ft.	51	...
8	Chunam plastering 2 coats ...	Sqr.	102'66	27'69
9	White and colour washing ...	"	102'66	27'69
10	Cement pointing to basement ...	"	5'85	2'10
11	Teakwood trusses with 1" Dr. tie rod struts 3" x 3" and Principals 3" x 5" as per design complete.	each	3	...
12	Teakwood wrought and put up with oiling ...	C.ft.	277'68	63'37
13	Roofing with first class Mangalore tiles on teak reapers nails, etc., complete.	Sqr.	19'58	...
14	Ridge tile set in mortar ...	R.ft.	117	...
15	Teakwood doors ½ panelled shutters 2/3 glazed shutters 1½" thick.	S.ft.	344	...
16	Teakwood windows half glazed shutters and half panelled with ¾" iron bars, hooks iron fittings, complete with top fan lights.	"	476	...
17	Teakwood ventilators with glazed shutters ...	"	98	23
18	Copal varnish two coats ...	Sqr.	8'96	4'07
19	Silicate painting ...	"	8'96	3'29
20	Teakwood eave boards ...	R.ft.	181	...
21	Flooring with first class Mangalore tiles on 3" concrete bed and pointed with cement (sterilizing).	Sqr.	20'49	2'08
22	Flooring with Cudapah slabs on 3" concrete bed and pointed with cement.	"	4'84	...

No.	Items of work	Per	Out patient Block quantity	Operation Theatre quantity
23	Painting walls of Operation Theatre ...	Sqr.	270	...
24	Providing sinks in dressing and Examination rooms and Operation, etc.	each	4	...
25	Cornice 9" thick with frieze work as per design ...	R.ft.	213	134
26	Inscription stone laying ceremony ..	Lumpsum	...	...
27	Drainage ..	"	...	...
28	Terrace brick in edge ..	Sqr.	1573	...
29	Parapet walls ..	R.ft.	198	131
30	Bressummer R. S. beams (3" x 5") 10 lbs. per R.ft. ..	Cwt.	10½	...
31	Ornamental work to windows outside ..	Lumpsum	...	No. 6
32	Counter arrangement for delivery of medicines ..	"	...	...
33	Archwork with brick in chunam ..	C.ft.	...	89
34	R. S. Beams 9' apart in centre 1½ cwt., load 32½ R.ft. ..	Cwt.	...	10
35	Roofing with pucca terrace including 1/15 in slope as per drawings.	S.qr.	...	645
36	Teakwood doors panelled shutters and four halves including fittings with ventilators at top with hinges screws 6" tower bolts stoppers iron clasps hooks, etc., complete.	S.ft.	...	92
37	Teakwood windows, half glazed and half panelled shutters iron bars frames 3" x 5" fittings rings hooks, etc., complete.	"	...	214
38	Teakwood wall shelves in operation room ..	"	...	39
39	Glazed tiles dadoing in operation Theatre, including fixing complete.	S.qr.	...	650
40	Sinks in bath rooms ..	Lumpsum	...	L. S.
41	Marble table ..	"	...	L. S.
42	Benches ..	each	...	4
43	Stone ware half pipe drains 4" diameter ..	R.ft.	...	95
44	Inscription of name ...	Lumpsum	...	L. S.

Approximate quantity for constructing *Two Wards* to the New District Hospital at Hassan.

No.	Items of work	Per	Quantity for one ward
1	Earthwork excavation ...	C.yd.	116
2	Concrete stone jelly in lime mortar ...	C.ft.	818
3	Burnt stone in chunam ...	"	2930
4	Burnt brick in mortar ...	"	3582
5	Burnt stone slabs 3" to 4" thick ..	S.ft.	474
6	Archwork brick in chunam ..	C.ft.	19
7	Plastering with chunam ...	Sqr.	8243
8	Teakwood trusses with 1½" tie rod, ¾" king rod, wooden principal 3" x 5" and struts 3" x 3" complete.	each	4
9	Teakwood work wrought and put up with oiling ..	C.ft.	20374
10	Roofing with first class Mangalore tiles on teak reapers nails, etc., complete.	Sqr.	2106
11	Ridge and hip tiles set in mortar ...	R.ft.	173
12	Pucca terrace ...	Sqr.	1151
13	Parapet wall ..	R.ft.	177
14	Cornice 7" ...	"	181
15	Eave boards plain 9" ...	"	259
16	Teakwood doors, 2/3 glazed and wirenetting ½ panel- led shutters, frame 3' x 5½" thick complete.	S.ft.	188
17	Teakwood half panelled and half glazed windows, iron bar, frame, etc., complete with glazed venti- lators at top.	"	210

No.	Items of work	Per	Quantity for one ward
18	Teakwood glazed ventilators for W. C.	S.ft.	30
19	Cement plastering	Sqr.	9'88
20	Glazed tiles fixed in cement	"	3'03
21	Flooring with first class Mangalore tiles 9" square on 3" concrete bed and pointed with cement.	"	11'77
22	Flooring with Cudapah slabs on 3" concrete bed and pointed with cement.	"	7'85
23	Cement pointing	"	5'94
24	Painting with silicate paint only outside of doors	"	4'28
25	Copal varnish inside	"	4'28
26	Inscription of name board	"	Lumpsum
27	Ornamental works to caps of pillars and unforeseen.	"	Lumpsum
28	Sanitary fittings	"	Lumpsum
29	Water-supply sinking a well	"	Lumpsum
30	Drainage	"	Lumpsum

Approximate quantity for constructing Sub-Assistant Surgeon's Quarters and Matron of the New District Hospital at Hassan (Two Blocks).

1	Earthwork excavation and filling in	C.yd.	36
2	Stone in clay. Foundation and basement	C.ft.	1497
3	Burnt brick in clay superstructure	"	1086
4	Burnt brick in chunam	"	348
5	Archwork brick in chunam	"	48
6	Burnt stone slabs 6" thick	S.ft.	119
7	Teakwood work wrought and put up	C.ft.	59'19
8	Rough plastering with chunam one coat $\frac{1}{2}$ " thick well rubbed with trowel and pressed with pebbles from the sand screenings thrown on the surface to get the effect of rough cast work.	Sqr.	43'20
9	Teakwood doors, frame of 3" x 5" and battened shutters with $\frac{3}{4}$ " battens and one inch planks including iron fillings locks, etc., complete.	S.ft.	144
10	Teakwood window frames 3" x 4" and battened shutters of $\frac{1}{2}$ " battens and $\frac{3}{4}$ " planks with iron fittings etc., complete.	"	36
11	Teakwood ventilators, glazed shutters complete	"	30
12	Roofing with first class Mangalore tiles on teak reepers, etc., complete.	Sqr.	12'40
13	Madras terrace	"	80
14	Parapet wall	R.ft.	24 $\frac{1}{2}$
15	Cornic 7" thick	"	25 $\frac{1}{2}$
16	Smooth plastering outside to pillars as per design	"	Lumpsum
17	Flooring with first class Mangalore tiles on 3" bed pointed with cement.	Sqr.	2'97
18	Flooring with Cudapah slabs on 3" concrete bed pointed with cement.	"	78
19	Flooring with chunam or unslaked lime or kanker well watered and tempered and smoothened as in Vajragarai.	"	2'03
20	Ridge tiles set in mortar	R.ft.	112 $\frac{1}{2}$
21	Jungle wood eaves board with painting	"	189
22	Pointing to basement	Sqr.	2'88
23	Coping with burnt brick in chunam and plastering complete.	R.ft.	65
24	Chocolate painting	"	Lumpsum
25	Unforeseen and clearing, gravelling and chimney arrangement and outlet.	Sqr.	4'80
26	Mortar and pestle	"	"
27	Constructing a bath room	"	"

Approximate quantity for constructing Quarters for Servants attached to the New District Hospital at Hassan. (Two Sweepers' Quarters).

No.	Items of work	Per	Quantity for two quarters
1	Earthwork excavation and filling in	Cyds.	16
2	Burnt stone in clay as per excavation	C.ft.	656
3	Burnt brick in clay	"	607
4	Burnt brick in chunam	"	154
5	Burnt stone slabs 3" to 4"	S.ft.	83
6	Teakwood wrought and put up	C.ft.	41.24
7	Plastering with mud	Sqr.	12.01
8	Rough plastering with chunam one coat	"	12.68
9	Chunam pointing to basement	"	1.85
10	Teakwood doors battened shutters complete	S.ft.	72
11	Teakwood windows, battened shutters iron bars, etc.	"	15
12	Roofing with Mangalore tiles on teak reepers nails, etc.	Sqr.	6.00
13	Flooring with granite slab for bath room	S.ft.	16
14	Coping with burnt brick in chunam complete	R.ft.	64
15	Graveling the floor	L. S.	
16	Smoke Ventilating tiles	Each	6
17	Eaves board jungle wood 6" x 1" thick	R.ft.	89
18	Ridge tiles set in mortar	"	66

Approximate quantity for constructing Quarters for Compounder and a Midwife attached to the New District Hospital at Hassan.

No.	Items of work	Per	Quantity for Two Blocks
1	Earthwork excavation	Cyds.	44
2	Concrete in lime mortar	C.ft.	313
3	Stone in clay Foundation and basement	"	1,115
4	Brick in clay	"	1,516
5	Burnt stone slabs 3" to 4" thick	S.ft.	98
6	Rough plastering with chunam one coat half an inch thick	Sqr.	40.28
7	Smooth plastering	"	L. S.
8	Teakwood work wrought and put up	C.ft.	42.12
9	Valleys with planks, zinc sheets, etc., complete	R.ft.	34
10	Roofing with Mangalore tiles on teak reepers	Sqr.	8.57
11	Ridge tiles set in mortar	R.ft.	46
12	Flooring with concrete in lime mortar and chunam plastering	Sqr.	3.86
13	Flooring with Cudapah slabs on 3" concrete beds and pointing with cement.	"	1.01
14	Teakwood battened doors	S.ft.	124
15	Do windows, iron-bars battened shutters	"	29
16	Coping with burnt brick in clay and chunam plastering	R.ft.	153
17	Chunam plastering	Sqr.	4.00
18	White and color washing	"	40.28
19	Painting with chocolate paint	"	3.00

Approximate quantity for constructing Mortuary attached to
Dispensary Building at Hassan.

No.	Items of work	Per	Quantity for One block
1	Earthwork excavation	C.yd.	25
2	Concrete in lime mortar	C.ft.	203
3	Foundation stone in clay	"	351
4	Burnt brick in clay	"	377
5	Stone slabs nicely dressed	"	44
6	Stone slabs 3" thick	S.ft.	43
7	Pointing with chunam	"	84
8	Plastering with chunam	Sqr.	6'31
9	White and colour washing	"	6'31
10	Stone flagging	"	1'44
11	Mangalore Tile roofing	"	3'87
12	Ventilating tiles	"	4
13	Teakwood work with oiling	No.	30'86
14	Teakwood doors battened	C.ft.	11'5
15	Teakwood windows with iron battened with shutters	S.ft.	10'5
16	Eaves Boards of jungle wood	"	79
17	Ornamental finials	R.ft.	2
18	Painting	No.	67
19	Honey comb work	Sqr.	241
20	Tarring	S.ft.	L. S.

Approximate quantity for constructing Latrines in the compound of the Dispensary at
Hassan. (Two Latrines).

No.	Items of work	Per	Quantity for one latrine
1	Earthwork excavation and filling in	C.yds.	4
2	Stone in chunam foundation and basement	C.ft.	911
3	Brick in clay	"	242
4	Plastering with chunam	"	4'43
5	White washing	Sqr.	4'43
6	Stone flagging	"	50
7	Tarring	"	2'42
8	Coping 1½' x ¾'	R.ft.	39

Approximate quantity for constructing a Kitchen in the compound of the
Dispensary at Hassan.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in	C.yd.	3
2	Stone in clay, Foundation	C.ft.	232
3	Brick in clay	"	279
4	Plastering with chunam	"	5'60
5	Whitewashing	Sqr.	5'60
6	Stone flagging	"	70
7	Roofing with Mangalore tiles	"	2'14
8	Ventilators	"	4
9	Teakwood work with oiling	S.ft.	12'17
10	Teakwood doors panelled	C.ft.	18
11	Teakwood windows panelled	S.ft.	5
12	Barge and eave boards	"	58
13	Ornamental finial	R.ft.	2
14	Painting	No.	45

Approximate quantity for constructing Office and Store in the New District
Hospital at Hassan.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in	Cyds.	15
2	Filling foundation with stone in chunam as per excavation ...	C.ft.	592
3	Burnt brick in clay	"	909
4	Burnt stone slabs 3" to 4" thick	S.ft.	58
5	Plastering with chunam two coats	Sqr.	17'04
6	Teakwood doors battened shutters, frame shingles lock, etc., complete.	S.ft.	49
7	Teakwood windows battened shutters frame, etc., complete with iron bars, hinges, locks and bolts, etc.	"	14
8	Teakwood ventilators, glazed shutters frame etc., complete ..	"	16
9	Teakwood work wrought and put up	C.ft.	24'49
10	Teak eaves board	R.ft.	88
11	Roofing with Mangalore tiles on teak reepers, nails, etc., complete.	Sqr.	5'44
12	Ridge tiles set in mortar	R.ft.	62
13	Cement pointing to basement	Sqr.	1'15
14	Flooring with square tiles on 3" concrete bed and pointed with cement.	"	2'20
15	Painting with silicate paint	"	1 53

Dated 17th December 1927.

"Reference is invited to the advertisement published in detail in the *Mysore Gazette*, dated 5th January 1928. The last date for receiving tender is 24th January 1928."

Dated 29—30th December 1927.

"Reference is invited to the advertisement published in detail in the *Mysore Gazette* of the 5th instant, advertising the date of tender will be received."

R. L. STEELE,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is hereby invited to the advertisement page No. 12 and 13 of the *Mysore Gazette* of 5th January 1928, calling for tenders for the work of constructing a Town Hall Building at Hanhar in Harihar Sub-Taluk.

A. TANDONI RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE RESIDENCY SURGEON, CIVIL AND MILITARY
STATION, BANGALORE.

Notice.

Notice is hereby given that sealed tenders will be received up to 12 noon on Wednesday the 15th February 1928 by the Residency Surgeon, Bangalore, for the supply by contract of all articles of diet, etc., required for the use of the Bowring and Lady Curzon Civil Hospitals and Dispensaries, Isolation Hospital and Hajee Sir Ismail Sait's Gosha Hospital, Bangalore, from 1st of April 1928 to 31st March 1929.

Form of tenders (which also contains the specifications and conditions on which tenders will be considered and contracts let) can be had at the office of the Residency Surgeon, Bowring Civil Hospital, Bangalore, on any day except Sundays, between 8 A.M. and 12 noon.

Each tender must be accompanied by a deposit (Government Promissory Notes or Bank Receipts) as earnest money of the amount noted against each group. When several groups are tendered for one Bank Receipt for the total amount of earnest money will be received. This earnest money will be returned to unsuccessful tenderers immediately and to the others as soon as they have lodged the security mentioned in paragraph 9 of the tender form. No cash will be received. In default of such deposit the tender will be rejected.

J. MC'PHERSON, Lt.-Col., I. M. S.,
Residency Surgeon, Bangalore,